

11-17-00

A

11/16/00
JCS12 U.S. PTO

LIMBACH & LIMBACH L.L.P.
2001 Ferry Building, San Francisco, CA 94111
415/433-4150

Address to:

Box Patent Application
Commissioner for Patents
Washington, D.C. 20231

Attorney's Docket No. SONY-U0438

First Named Inventor KOUICHI MATSUDA

UTILITY PATENT APPLICATION TRANSMITTAL
(under 37 CFR 1.53(b))

SIR:

Transmitted herewith for filing is the patent application entitled:
SHARED VIRTUAL SPACE CONVERSATION SUPPORT SYSTEM AND METHOD AND PROGRAM
RECORDING MEDIUM

CERTIFICATION UNDER 37 CFR § 1.10

I hereby certify that this New Application and the documents referred to as enclosed herein are being deposited with the United States Postal Service on this date November 16, 2000, in an envelope bearing "Express Mail Post Office To Addressee" Mailing Label Number EL776051253US addressed to: Box Patent Application, Commissioner for Patents, Washington, D.C. 20231.

Susan Ozanne

(Name of person mailing paper)

(Signature)

Enclosed are:

1. ☒ Transmittal Form (two copies required)
2. The papers required for filing date under CFR § 1.53(b):
 - i. 65 Pages of specification (including claims and abstract);
 - ii. 14 Sheets of drawings.
 ☐ formal ☒ informal
3. Declaration or oath
 - a. ☒ Unsigned - Combined with Power of Attorney

ACCOMPANYING APPLICATION PARTS

4. ☐ An assignment of the invention to Sony Corporation is attached (including Form PTO-1595).
 - i. ☐ 37 CFR 3.73(b) Statement (when there is an assignee)
5. ☒ Power of Attorney - Unsigned - Combined with Declaration
6. ☐ An Information Disclosure Statement (IDS) is enclosed, including a PTO-1449 and copies of ☐ references.
7. ☐ Preliminary Amendment.
8. ☒ Return Receipt Postcard (MPEP 503 -- should be specifically itemized)
9. FOREIGN PRIORITY
 - [x] Priority of application no. P11-337105 filed on November 29, 1999 in Japan is claimed under 35 USC 119.

The certified copy of the priority application:

- ☒ is filed herewith; or
☐ has been filed in prior application no. ☐ filed on ☐, or
☐ will be provided.

☐ English Translation Document (if applicable)

JCS12 U.S. PTO
09/714637
11/16/00

09744637 11/16/00

10. FEE CALCULATION

- a. ☐ Amendment changing number of claims or deleting multiple dependencies is enclosed.

CLAIMS AS FILED

	Number Filed	Number Extra	Rate	Basic Fee (\$710)
Total Claims	21 - 20	* 1	x \$18.00	80.00
Independent Claims	10 - 3	* 7	x \$80.00	560.00
<input type="checkbox"/> Multiple dependent claim(s), if any			\$270.00	0

*If less than zero, enter "0".

Filing Fee Calculation \$1,288.00

50% Filing Fee Reduction (if applicable) \$

11. Small Entity Status

- a. ☐ A small entity statement is enclosed.
b. ☐ A small entity statement was filed in the prior nonprovisional application and such status is still proper and desired.
c. ☐ is no longer claimed.

12. Other Fees

- ☐ Recording Assignment [\$40.00] \$0
☐ Other fees
Specify _____ \$0

Total Fees Enclosed \$1,288.00

13. Payment of Fees

- ☒ Check(s) in the amount of \$ 1,288.00 enclosed.
☐ Charge Account No. 12-1420 in the amount of \$____.
A duplicate of this transmittal is attached.

14. All correspondence regarding this application should be forwarded to the undersigned attorney:

Charles P. Sammut
Limbach & Limbach L.L.P.
2001 Ferry Building
San Francisco, CA 94111
Telephone: 415/433-4150
Facsimile: 415/433-8716

15. Authorization to Charge Additional Fees


- ☒ The Commissioner is hereby authorized to charge any additional fees (or credit any overpayment) associated with this communication and which may be required under 37 CFR § 1.16 or § 1.17 to Account No. 12-1420. **A duplicate of this transmittal is attached.**

LIMBACH & LIMBACH L.L.P.

November 16, 2000
(Date)

Attorney Docket No. SONY-U0438
[S00P1438US00]

By:


Mark C. Pickering
Registration No. 36,239
Attorney(s) or Agent(s) for Applicant(s)

SHARED VIRTUAL SPACE CONVERSATION SUPPORT SYSTEM
AND METHOD AND PROGRAM RECORDING MEDIUM

BACKGROUND OF THE INVENTION

09744637 111500

The present invention relates generally to a conversation support system and a conversation support method for supporting a virtual conversational environment in which a plurality of users can participate, the system and the method being built and provided on a computer network such as the Internet. More especially, the present invention relates to a conversation support system and a conversation support method for supporting a virtual conversational environment in which a plurality of users can participate in a virtual world having a predetermined spatial expanse built on a computer network.

To be more specific, the present invention relates to a conversation support system and a conversation support method for allowing users to communicate with each other without actually meeting each other in a shared virtual world having a spatial expanse built on a computer network and, more particularly, to a conversation support system and a conversation support method for allowing users to communicate with each other in virtual worlds beyond the framework of a single shared

virtual world.

Recently, remarkable advances in computing technologies in information processing and information communication have been made and, on the basis thereof, computer systems have become widespread. Also, demands for network computing technologies for interconnecting computers have been growing. On networks, users of computers can smoothly share computer resources and share, distribute and exchange information. In addition, computer users can carry out collaborative work on their computers interconnected by networks.

Computers are interconnected by various types of networks. For example, these networks include LANs (Local Area Networks) such as Ethernet and Bluetooth, a WAN (Wide Area Network) formed by interconnecting LANs by leased lines for example, and the Internet which has grown to a worldwide network as a result of repeatedly interconnecting smaller networks.

The Internet is a network which has evolved from the ARPANET (Advanced Research Projects Agency Network) built by the U.S. Department of Defense. From the ARPANET, the Internet was then included in NSFNET (National Science Foundation Network) of U.S. National Science Foundation. Further, with the backbone of NSFNET

transferred to nongovernment organizations in 1995, the fully fledged expansion known today of the Internet started. The Internet has grown to the today's gigantic network as a result of the repetition of autonomous interconnections of servers (mainly UNIX workstations) installed in universities and research organizations. The servers on the Internet are interconnected normally on the basis of TCP/IP (Transmission Control Protocol/Internet Protocol). Currently, millions of servers are connected to the Internet, each server making public its various resource objects to countless clients.

On the Internet, many services such as the WWW (World Wide Web), News, TELNET (TELEtypewriter NETwork), FTP (File Transfer Protocol), and Gopher for example are provided for the general public. Of these services, WWW is a worldwide information search system providing an information space having a hyperlink structure and the main factor for the explosive growth and fast popularization of the Internet.

The WWW, invented by Tim Bernes-Lee at CERN (European Center for Nuclear Research) of Switzerland, is a worldwide information search system that allows accessing various media such as text, image, and voice in the form of hypertext. The hypertext information handled

on the WWW is described in a hypertext description language called HTML (Hyper Text Markup Language). According to HTML-based hypertext description, the logical structure of document can be expressed by formatting delimited basically by "<" and ">". A protocol used for transferring HTML files on TCP/IP networks is called HTTP (Hyper Text Transfer Protocol).

Currently, countless number of HTML documents, namely information resources, are presented with and without charge on the Internet. According to TCP/IP, various information resources including these HTML documents are identified by identifiers having a format called URL (Uniform Resource Locators). A URL is character string specifying means for accessing an information resource and the name thereof and described in the form of "scheme name (protocol name)://host name (domain name): port number/pass number (file name)". An HTML document can include a link relationship with another information source, the link information also being specified in the form of URL.

The WWW is a system constructed in a client-server model. A WWW server is a computer system that operates server software called an HTTP daemon and stores and/or provides information resources described in HTML form

(the daemon generically denotes programs that execute system management and processing in the background in UNIX environment).

A WWW client is a computer which operates by use of a user agent called a WWW browser or an HTML browser. Typical WWW browsers are "Netscape Navigator" of Netscape Communications and "Internet Explorer" of Microsoft Corp.

A WWW client user can specify desired information resources by entering a URL character string into a location box on a WWW browser screen. Normally, a WWW browser accesses or retrieves information resources on WWW servers in accordance with HTTP (Hyper Text Transfer Protocol). Besides, a WWW browser analyzes a retrieved HTML document and displays its contents on the browser window screen (namely, a home page is constructed on the browser screen). On a WWW page displayed on the browser screen, link information is indicated as "anchor". The user clicks this anchor can specify an information resource of next reference destination. That is, via a WWW browser screen, the user searches a WWW information resource space in which hyper links are woven on the Internet to sequentially access various desired information resources.

In addition to the WWW, various applications such

as BBS (Bulletin Board System) and chatting are available on the Internet.

A BBS is a system by which computerized bulletin information is accumulated on a server on a network and the accumulated information is made available for the viewing by users through the network. A BBS allows the centralized management of information on a server and the realtime exchanging of information between remotely distributed users.

Chatting is an online talking system which allows realtime conversation between users through keyboard inputted words via a network. Normally, two or more users log in a chat for a simultaneous talk in which remarks made by one user are displayed on the monitor screens of all users. Chatting allows remotely distributed users to make realtime conversation and discussion in a virtual world constructed on the Internet. Only logging in a virtual world provided by a chatting system instantly qualifies users to join a chat session. Besides, the users participating in a chat session need not be known by sight in the real world. These are major advantages of chatting. While the interaction by BBS is asynchronous, the conversation by chat is synchronous and therefore each participant can make remarks while checking the

reactions of chatting mates, which makes the communication livelier than BBS.

For example, a cyberspace service named Habitat (trademark) is known in the so-called personal computer communications services. Development of Habitat started in 1985 by Lucas Film of the US, operated by Quantum Link, one of US commercial networks, for about three years. Then, Habitat started its service in NIFTY-Serve as Fujitsu Habitat (trademark) in February 1990.

In Habitat, users can send their alter egos called avatars (the incarnation of a god figuring in the Hindu mythology) into a virtual city called Populopolis drawn by two-dimensional graphics to have a chat (namely, a realtime conversation based on text entered and displayed) with each other. For further details of Habitat, refer to the Japanese translation of "Cyberspace: First Steps," Michael Benedikt, ed., 1991, MIT Press Cambridge, MA, ISBN0-262-02327-X, the translation being published March 20, 1994, by NTT Publishing, ISBN4-87188-265-9C0010, pp. 282-307.

Meanwhile, the information resources handled on the Internet were initially nothing but two-dimensional, flat representations. For example, the HTML documents handled on the WWW system only describe two-dimensional

information. Therefore, the HTML content displayed on an HTML browser screen, or a home page screen, is nothing but two-dimensional, flat representation.

In the conventional cyberspace systems operated by personal computer communications services such as mentioned above, a virtual reality street and the inside of a room for example are drawn in two-dimensional graphics. Therefore, moving an avatar in the depth direction is realized simply by moving it up and down in the background of the two-dimensional graphics. This results in a poor expression in simulating walking and movement in a virtual reality space. Also, the two-dimensional virtual reality space in which own avatar and the avatar of another user are displayed is viewed from a viewpoint of a third party, thereby impairing the sense of simulated experience.

On the other hand, VRML (Virtual Reality Modeling Language) was developed as a language to enable the description of three-dimensional information and the setting of hypertext links for objects drawn by three-dimensional graphics by extending the WWW. VRML allows to handle the appearance (for example, a lighting condition) and geometry of a three-dimensional object as data. In addition, VRML can assign a name to an object to describe

the action of the name in a Java programming language.

VRML 1.0 allows mainly the still object representations in which a three-dimensional object changes in response to a mouse operation by the user. VRML 2.0, for which the specifications based on "moving world" were made public, adds three-dimensional object autonomous behavior, animation mapping, audio data handling, interactive representations for example. Details of VRML are disclosed in the Japanese translation of "VRML: Browsing & Building Cyberspace," Mark Pesce, 1995, New Readers Publishing, ISBN1-56205-498-8, the translation being entitled "Getting to Know VRML: Building and Browsing Three-Dimensional Cyberspace," translated by Kouichi Matsuda, Teruhisa Kamachi, Akikazu Takeuchi, Yasuaki Honda, Junichi Rekimoto, Masayuki Ishikawa, Ken Miyashita and Kazuhiro Hara, published March 25, 1996, Prentice Hall, ISBN4-931356-37-0 for example.

The official and complete specifications of VRML 2.0 are publicized at "<http://webpace.sgi.com/moving-worlds/spec/index.html>" and the Japanese version thereof is publicized at "<http://www.webcity.co.jp/info/andoh/VRML/vrml2.0/spec-jp/index.html>."

Construction of a three-dimensional virtual space by use of VRML 2.0 requires to only create a VRML file as follows:

- (1) create graphic data indicative of the geometry, motion, and position of an object (or a model) in the virtual space (this process is called modeling);
- (2) add a switch (or a sensor) to the model for generating an event in response to a mouse operation by user in which the user clicks the model in the displayed virtual space (this process is called sensor addition);
- (3) program a script for realizing an event in response to the operation by user on the sensor (this processing is called scripting); and
- (4) relate sensor operation with script activation and graphic data with the script (this processing is called routing).

VRML content can be accessed by use of a VRML browser. Namely, desired VRML content can be read from a WWW resource space on the Internet to be displayed through a VRML browser. The user can roam about in the displayed three-dimensional space by use of a pointing device such as a mouse. As the user moves in the displayed three-dimensional space, the displayed screen changes realtime to a scene viewed from each moving

position. Movement in a narrow range is displayed by re-computing the three-dimensional data on the client side. A hypertext link may be set to an object (for example, a cuboid or a column) drawn by use of three-dimensional graphics. Namely, the user can search a three-dimensionally displayed screen with a mouse cursor to reach another item of VRML content or HTML content by clicking an anchor displayed represented in a three-dimensional object.

For example, VRML allows the description of a three-dimensional shared virtual space to be shared by two or more users. The above-mentioned chatting was initially a system by which words inputted by participants through their keyboards are only sequentially recorded. Also, the cyberspaces were initially nothing more than two-dimensional graphic representations. Recently, however, a three-dimensional chatting system has appeared in which participants have conversations a three-dimensional virtual space, providing a place of communication in a shared virtual society abounding with realistic touches built and provided on the Internet.

A three-dimensional shared virtual space is described in VRML and can be downloaded from a WWW server

through the Internet for example. Each participant who logs in a shared virtual space is allocated with an avatar, which is equivalent to the alter ego of the user. The avatar is a type of an application object generated by an application program. Information (for example, current position, attire, name, and gender) about each avatar in a shared virtual space is shared among the log-in users, so that the avatars of own and other users appear on the monitor screen of each user. Each user can make his avatar search the shared virtual space as if the user himself searched the real world. Remarks inputted by a user through the keyboard are displayed on the monitor screen of all participating users in the form of a speech balloon popping up from the avatar of the remarking user.

Three-dimensional shared virtual worlds can visually attract more users than old-fashioned chatting systems in which remarks made by users are only displayed in text in a time series manner. Each three-dimensional shared virtual space also allows users to check realtime the reactions of others through three-dimensional graphical representation, thereby making conversations livelier. The participating users can share virtual or pseudo experiences such as events that take place in the shared virtual world. In addition, the participating

users can execute game-like interactive operations such as searching for other avatars or escaping from them in the three-dimensional space. Further, introduction of time mechanisms for providing day and night and seasons for example and other changes simulating the real world enhances the sense of virtual reality, thereby providing a user-friendly environment in each shared virtual space.

USP 5,956,038 (equivalent to Japanese Patent Laid-open No. Hei 9-81781) assigned to the applicant hereof for example discloses a three-dimensional virtual reality space system in which users can roam about by use of the viewpoints of their avatars in a three-dimensionally expressed shared virtual space. This shared virtual space can be described by use of a VRML description language.

Each three-dimensional shared virtual space is high computerized and therefore, as compared with a physical real world, virtual social infrastructures can be built more easily by computer processing. For example, a calling card system by which calling cards and other information are exchanged among avatars, a distribution system (for example, virtual shop, virtual currency, and virtual barter), a virtual space mailing system may be introduced (for example, Japanese Patent Laid-open No. Hei 11-203009 assigned to the applicant hereof equivalent

to US application for patent No. 09/227689 discloses the introduction of calling cards in a shared virtual space.) Namely, passing a calling card to the virtual creature object bred by a user not accessing the shared virtual spaces can realize communication between users. Further, the three-dimensional shared virtual space can extend the activity radius of each avatar and expand a shared virtual space to accommodate more log-in users, or avatars.

As described, positional information and other information associated with avatars existing in a shared virtual space is shared by the log-in users, each user being capable of observing the avatars of own and other users on the monitor screen. However, distribution of the information about an expansive shared virtual space in its entirety to users is difficult or impracticable due to such physical constraints in the Internet as line bandwidth. The distance between avatars implies the degree of interest and intimacy between users and therefore the information about avatars separated far away from own avatar may be unnecessary for that user to have.

Consequently, a so-called aura algorithm scheme is employed in which, generally, only the information inside

an area of interest, namely an aura, is transferred to each user, the information outside the aura being prevented from distribution. Generally, an aura is defined on the basis of the current position of an avatar. For the details of the aura algorithm, refer to, for example, Beford, S., and Fahlen, L., "A Spacial Model of Interaction in Large Virtual Environments," Proc. Of G. DeMichelis et al. (Eds.), Third European Conference on Computer Supported Cooperative Work, Kluwer Academic Publishers, pp. 109-124, 1993.

Introducing the concept of aura into a shared virtual society can reduce the volume of data to be distributed to each user, at cost that communication with users outside that aura is disabled because the extra-aura information is not transferred to the users inside the aura.

An avatar symbolizing each user is living in a shared virtual space while almost always moving, chasing or escaping other avatars for example. Therefore, the supply of information about an avatar getting outside the aura is discontinued and, if this happens, there is no way of communicating with it.

To overcome this drawback, a virtual communications infrastructure called "mobile phone" is introduced in a

shared virtual space to acquire a method of communicating with avatars outside the aura or remotely separated avatars. This method allows each avatar, regardless of inside or outside the aura, can establish communication with others by dialing their mobile phones. In the real world also, the telephone denotes a device for supporting realtime communication between remotely separated users. In having conversations by use of virtual mobile phones, an avatar need not at all bring a mate avatar into the own aura. The virtual mobile phone also allows direct communication with avatars which are missing inside the aura.

The virtual mobile phone introduced in a shared virtual space (hereafter also referred to as a virtual telephone) not only realizes one-to-one realtime communication between avatars in the same shared virtual space but also may have the basic features of the mobile phone of the real world. For example, these features include a telephone directory capability by which the names and telephone numbers are registered beforehand and only a registered name need to be selected for dialing, an incoming call rejection directory capability by which specific users are registered beforehand to reject the receipt of their calls, and a nuisance call rejection

capability by which the calls from the specified users registered in the incoming call rejection directory are rejected.

Use of the virtual telephone makes it unnecessary for each avatar to remain inside its aura to establish communication with each other. Namely, use of the virtual telephone allows each user to communicate with avatars which is outside the aura or the monitor screen, thereby making it unnecessary for each user to search the immense virtual shared space for companionship with other avatars or users.

If avatars make an agreement for meeting some day in the shared virtual space, the possibility of the reunion is low unless the place and time of the meeting are set. Use of the virtual telephone eliminates this necessity for the place and time setting because the avatars equipped with the virtual telephone only need to be exist in the same shared virtual space at the same time. In addition, the virtual telephone makes it unnecessary for each user to make a direct, face-to-face contact with the avatar of another user for passing a message.

Originally, the telephone is for remote communication. Therefore, some users want to make avatar

communication not only inside a single virtual space, but also with other virtual spaces and even with the real world.

For example, a user who cannot log in a chat system, namely cannot enter a shared virtual space, due to some urgent business or the like may want to talk with another avatar, namely a user who is logging in the chat system. In another example, if the avatar of another user does not appear in a shared virtual space at an appointed time, namely the user of that avatar is not logging in the chat system, the mate user may want to send a message to that log-off user.

A virtual shared space itself is constructed in a distributed computing environment such as the Internet in which many computers are networked. A gateway to another world beyond a single virtual space is obviously desired by its users.

SUMMARY OF THE INVENTION

It is therefore an object of the present invention to provide a conversation support system and a conversation support method that allow two or more users to simultaneously participate, for realtime communication, in a virtual world having a predetermined spatial expanse

built on a computer network such as the Internet.

It is another object of the present invention to provide a conversation support system and a conversation support method that allow users to communicate each other without making a face-to-face meeting in a shared virtual world having a spatial expanse built on a computer network.

It is still another object of the present invention to provide a conversation support system and a conversation support method that allow users to communicate each other beyond a single shared virtual world.

It is yet another object of the present invention to provide a conversation support system and a conversation support method that allow users to communicate each other even if one of users between whom communication is to be established is not in a shared virtual world having a spatial expanse built on a computer network.

In carrying out the invention and according to a first aspect thereof, there is provided a conversation support system or method for supporting a plurality of users in having a virtual conversation in a shared virtual space built and provided on a computer network,

comprising: enrolling means or step for enrolling an avatar of a log-in user into the shared virtual space; imparting means or step for imparting a virtual mobile telephone to each avatar in the shared virtual space, the virtual mobile telephone being usable therein; determination means or step for determining, in response to a call from the virtual mobile telephone, whether a calling party who originated the call exists in the shared virtual space; and connecting means or step for executing connection processing in accordance with a decision made by the determination means.

If the calling party originated the call from a telephone in real world, the connecting means or step establishes connection with the calling party through a public telephone network in real world and/or executes message transfer.

If the calling party originated the call from a telephone in another virtual space, the connecting means or step establishes connection with the telephone in another virtual space and/or executes message transfer.

The connecting means or step receives the call from the telephone in real world and/or the telephone in another virtual space and connects the received call to a virtual mobile telephone of a called avatar in the shared

virtual space. In this case, when the call comes from the telephone in real world or the telephone in another virtual space, it is determined whether this call is addressed to an avatar existing in the shared virtual space. If the decision is affirmative, the call is connected to the virtual telephone of that avatar.

In carrying out the invention and according to a second aspect thereof, there is provided a conversation support system or method for supporting a plurality of users in having a virtual conversation in a shared virtual space built and provided on a computer network, comprising: enrolling means or step for enrolling an avatar of a log-in user into the shared virtual space; imparting means or step for imparting a virtual public telephone usable by any enrolled avatar to the shared virtual space at a predetermined place; determination means or step for determining, in response to a call from the virtual public telephone, whether a calling party who originated the call exists in the shared virtual space; and connecting means or step for executing connection processing in accordance with a decision made by the determination means.

If the calling party originated the call from a telephone in real world, the connecting means or step

establishes connection with the calling party through a public telephone network in real world and/or executes message transfer.

If the caller originated the call from a telephone in another virtual space, the connecting means or step establishes connection with the telephone in another virtual space and/or executes message transfer.

In carrying out the invention and according to a third aspect thereof, there is provided a conversation support method for supporting an activity of an avatar in a shared virtual space built and provided on a computer network, comprising the steps of: receiving a request for sending a message from the avatar; determining whether a destination of the message exists in the shared virtual space; and executing connection processing in accordance with a decision made by the determining step.

If the destination of the message is found in real world, the connecting step establishes connection with the destination through a public telephone network in real world and/or executes message transfer.

In carrying out the invention and according to a fourth aspect thereof, there is provided a conversation support method for supporting an activity of an avatar in a shared virtual space built and provided on a computer

network, comprising the steps of: receiving a request for sending a message from a source in real space through a public telephone network in real world; determining whether a destination of the message exists in the shared virtual space; and if a decision made in the determination step is affirmative, sending the message to the avatar.

In carrying out the invention and according to a fifth aspect thereof, there is provided a program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, the computer program comprising the steps of: enrolling an avatar of a log-in user into the shared virtual space; imparting a virtual mobile telephone usable by any enrolled avatar to the shared virtual space at a predetermined place; determining, in response to a call from the virtual mobile telephone, whether a calling party who originated the call exists in the shared virtual space; and executing connection processing in accordance with a decision made in the determination step.

In carrying out the invention and according to a

sixth aspect thereof, there is provided a program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, the computer program comprising the steps of: enrolling an avatar of a log-in user into the shared virtual space; imparting a virtual public telephone usable by any enrolled avatar to the shared virtual space at a predetermined place; determining, in response to a call from the virtual public telephone, whether a calling party who originated the call exists in the shared virtual space; and executing connection processing in accordance with a decision made in the determination step.

In carrying out the invention and according to a seventh aspect thereof, there is provided a program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, the computer program comprising the steps of: receiving a request for sending a message from the avatar;

determining whether a destination of the message exists in the shared virtual space; and executing connection processing in accordance with a decision made in the determination step.

In carrying out the invention and according to an eighth aspect thereof, there is provided a program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, the computer program comprising the steps of: receiving a request for sending a message from a source in real space through a public telephone network in real world; determining whether a destination of the message exists in the shared virtual space; and, if a decision made in the determination step is affirmative, sending the message to the avatar.

A user who has logged in the shared virtual world associated with the invention can send an avatar of the user into the shared virtual world. A so-called aura algorithm scheme is applied to each user computer, in which, generally, only the information inside an area of interest, namely an aura, is transferred to each user,

the information outside the aura being prevented from distribution.

The aura algorithm has a drawback that communication is interrupted if the mate avatar gets out of the aura. To overcome this drawback, such an infrastructure is introduced to the shared virtual world as a mobile telephone, a PHS, or a public telephone that realizes remote communication at any given place.

According to the invention, each avatar can use its telephone such as a PHS to make communication not only in the same shared virtual world but also with another virtual world or the real world.

Therefore, a user who cannot log in a chat system at an appointed time, namely cannot enter a shared virtual world, due to some urgent business or the like may talk with another avatar, namely a user who is logging in the chat system through a PHS in the real world.

In another example, if the avatar of another user does not appear in a shared virtual space at an appointed time, namely the user of that avatar is not logging in the chat system, the mate user may send a message to that log-off user in the real world.

Further, an avatar can communicate through its PHS

with an avatar living in another virtual world. In other words, avatars can use the infrastructure such as a PHS to make communication beyond a single virtual space.

The program storage media associated with the fifth through eighth aspects of the invention provide a computer program in a tangible and computer-readable form to a general-purpose computer system which can execute various program codes for example. The program storage media include a CD (Compact Disc), an FD (Floppy Disc), an MO (Magneto-Optical disc), a DVD (Digital Versatile Disc), and other detachable and portable storage media. The computer program may also be distributed through transmission media such as a network (regardless of cabled or wireless and regardless of terrestrial wave or satellite wave) including a LAN and the Internet.

The above-mentioned program media define the cooperative relationship in structure or function between computer program and providing medium for realizing the function of a predetermined program on a computer system. In other words, installing a predetermined program into a computer system by way of the program media associated with the fifth through eighth aspects calls forth the above-mentioned cooperative relationship, thereby providing the same effects as those of the first through

fourth aspects of the invention.

The above and other objects, features and advantages of the present invention and the manner of realizing them will become more apparent, and the invention itself will best be understood from a study of the following description and appended claims with reference to the attached drawings showing some preferred embodiments of the invention.

BRIEF DESCRIPTION OF THE DRAWINGS

These and other objects of the invention will be seen by reference to the description, taken in connection with the accompanying drawing, in which:

FIG. 1 is a schematic diagram illustrating a configuration of a network computing system capable of constructing and providing a shared virtual space suitable for realizing the present embodiment;

FIG. 2 is a schematic diagram illustrating a behavior architecture for displaying and navigating the shared virtual world associated with the present invention on a computer of a user who has logged in this shared virtual world;

FIG. 3 is a schematic diagram illustrating an operation mechanism of an AO associated with the

invention; to be more specific, FIG. 3 illustrates an example of an operation caused by clicking a pet (a shared application) of the avatar of a user who has logged in a shared virtual space;

FIG. 4 is a schematic diagram illustrating a condition in which communication with an avatar outside an aura cannot be executed in a shared virtual space;

FIG. 5 is a schematic diagram illustrating a manner in which communications with an avatar outside an aura is executed by use of a telephone in a shared virtual world; to be more specific, FIG. 5 shows a manner of communication by use of a mobile telephone in a virtual world;

FIG. 6 is a schematic diagram illustrating a manner in which communication with an avatar outside an aura is executed by use of a telephone in a shared virtual world; to be more specific, FIG. 6 shows a manner of communication by use of a public telephone in a virtual world;

FIG. 7 is a schematic diagram illustrating a manner in which an avatar inside a shared virtual space associated with the present invention communicates with a user in another virtual world by use of a virtual telephone;

FIG. 8 is a schematic diagram illustrating a manner in which an avatar inside a shared virtual space associated with the present invention communicates with a user in the real world by use of a virtual telephone;

FIG. 9 is a diagram illustrating a GUI (Graphical User Interface) screen (a CP browser window) provided on a computer 100 of a user who has logged in a community system associated with the present invention;

FIG. 10 is a diagram illustrating a picture in which "Telephone Directory" window appeared on the CP browser screen;

FIG. 11 is diagram illustrating a communications tool displayed on the CP browser screen when a shared virtual space is searched for a public telephone box and it is accommodated in an aura;

FIG. 12 is a diagram illustrating a picture in which "PHS Talk" window popped up in response to the clicking of "Call" button in "Telephone Directory" window;

FIG. 13 is a flowchart indicative of a procedure of processing to be executed when a user in a shared virtual world makes a call through the avatar of the user; and

FIG. 14 is a flowchart indicative of a procedure of processing to be executed when a user makes a call from

the real world to an avatar living in a shared virtual world.

DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS

This invention will be described in further detail by way of example with reference to the accompanying drawings.

1. Configuration of Community System

Now, referring to FIG. 1, there is shown the configuration of a network computing system 1 capable of building and providing a shared virtual world suitable for realizing the present invention. As will be described, a community system to be developed into a three-dimensional shared virtual world is built and provided on this network computing system 1. This community system comprises three components; a browser (a CP browser) for displaying and navigating a virtual space, a shared virtual world server (a CP server) for managing the virtual space, and an AO (Application Object) providing an environment for the development of shared applications.

The network computing system 1 is connected to many computer systems. These computer systems are distributed all over the world, some of them operating as servers that provide various services with charge or without

charge and others operating as clients that request servers for particular services.

As shown in FIG. 1, the network computing system 1 includes, as communication media, the Internet 10, LANs (Local Area Networks) 20A, 20B, and so on as small-scale networks, and a public telephone network 30 constructed and provided by a telephone company of each country. Obviously, the entity of each of the LANs may be a single network segment or a plurality of segments interconnected by routers.

The Internet 10 is connected to the LANs 20A and 20B by routers 21A and 21B respectively. The entity of the Internet 10 is, as described before, a vast network grown globally from repeating the interconnections of the servers of the small-scale networks. The servers in the Internet 10 and the small-scale networks are accessible each other in accordance with a predetermined communications protocol such as TCP/IP (Transmission Control Protocol/Internet Protocol).

The Internet 10 and the LANs are connected to a public telephone network 30 through a gateway system 40. The public telephone network 30 includes PSTN (Public Switched Telephone Network) and ISDN (Integrated Service Digital Network) for example.

The public telephone network also accommodates many exchanges and end offices, both not shown. The end offices are connected to subscriber telephones. With the public telephone network 30, many wireless telephone networks are installed by many such carriers providing wireless communications services as a mobile telephone service provider, a PHS (Personal Handy-phone System) service provider, and a pager service provider.

The computer systems on the Internet 10 have each an IP address identifiable on the Internet. In other words, the IP address provides a logical connection between each computer and the Internet 10.

On the Internet 10, there are also Internet service providers (ISPs) for providing services for connecting to the Internet the general users who cannot execute the IP connection by leased line. The profit making Internet service providers must be officially registered as a type-2 telecommunications business. One of ISPs is So-net (trademark). So-net allows general users to dial up its server, or access point (AP), to execute the IP connection to the Internet (this is called dial-up IP connection), so that the general users are freed from an economical burden of acquiring own IP address.

A personal computer (PC) 100 of a general user IP-

connected via a given Internet service provider operates mainly as a client on the Internet 10 and can request the WWW (World Wide Web) server and other various servers for various services.

Generally, in addition to the dial-up IP connection service, Internet service providers provides various applications such as chat, BBS (Bulletin Board System), and electronic mail on the Internet 10.

Obviously, various parent organizations other than Internet service providers can provide Internet applications such as chat, BBS, and electronic mail.

In the example shown in FIG. 1, an Internet service provider operating the LAN 20A provides a community system associated with the present invention. In this community system, users can make virtual reality communication such as chat by means of avatars in a three-dimensional shared virtual world.

Chat is a service for providing realtime communication between remote users through the Internet 10. Especially, three-dimensional chat provides a realtime communication environment in which each log-in user sends his or her avatar into a three-dimensional shared virtual world drawn by three-dimensional graphics for realtime communication with other log-in users. A three-

dimensional shared virtual world, or the community system, on a WWW system can be described by VRML (Virtual Reality Modeling Language) 97 of ISO (International Organization for Standardization) for example. The activities in the community system can be described by use of Java. Three-dimensional shared virtual worlds thus described can be displayed and navigated by use of VRML browsers. For details of VRML 97, refer to

"<http://www.vrml.org/Specifications/VRML97/>".

The LAN 20A is arranged with a shared virtual world (the Community Place (CP)) server 22 for building and providing a shared virtual world on the Internet 10, providing an environment in which various social activities are performed in the shared virtual world, and managing the shared virtual world and one or more application object (AOs) servers 23-1, 23-2, and so on.

The LAN 20 A may also be arranged with one or more WWW servers 25 and so on for providing HTTP (Hyper Text Transfer Protocol) resource objects such as HTML (Hyper Text Markup Language) content and a mail server 26 for providing an electronic mail transfer service. The servers 22, 23-1, 23-2, 25, and 26 arranged on the LAN 20A can be accessed from the Internet 10 through the router 21A.

In the present embodiment, the WWW server 25 provides a VRML file describing the three-dimensional virtual world in addition to the ordinary HTML content. This VRML file also contains the descriptions of the virtual world and shared applications, the address (uniform resource locator URL) of the shared virtual world (CP) server 22 or its link reference.

The computer (PC) 100 of the user who logs in the three-dimensional shared virtual world associated with the present embodiment has both of an HTML browser for browsing the HTML content provided by the WWW server 25 and a VRML browser for handling VRML files. The VRML browser used in the present embodiment is also called a CP browser because it displays and navigates a shared virtual world (the Community Place (CP)). The HTML browser and the CP browser can be operated on a same platform provided by Windows 95, Windows 98, or NT of Microsoft Corp. for example. The user computer 100 itself is constituted by an PC/AT (Personal Computer/Advanced Technology) or its succeeding versions or their compatibles.

A three-dimensional shared virtual world constructed by use of VRML allows each object arranged therein to realize an autonomous action, namely a

behavior, in response to an event taking place in response to a user operation and a timer event taking the passing of preset time.

A behavior is realized by the cooperative actions of three elements; sensor, routing and script.

(1) A sensor node related beforehand with a node of an object for example disposed in a three-dimensional world and described as a VRML file senses an external event on the basis of a change of its field generates an event inside a VRML scene.

(2) The generated event is routed or transmitted to an external script, which is a program for specifying the behavior of the object, on the basis of a routing described as a VRML file.

(3) In the external script, a method to be called at arrival of the event is described beforehand. The external script which received the event transmitted by routing executes the processing based on the description and then changes the field value of a corresponding node inside the VRML scene on the basis of a result of the processing and the description of the routing.

VRML defines, as sensor nodes, TouchSensor for generating event when a mouse cursor passes over a specified object or when it is clicked, ProximitySensor

for generating an event when user viewpoint enters a specified area, and TimerSensor for generating an event every time a predetermined time is reached or a predetermined time interval passes, for example.

2. Behavior Architecture of Community System

FIG. 2 shows a behavior architecture for displaying and navigating a shared virtual world associated with the present embodiment on the computer 100 of the user who logs in this shared virtual world. As described, on the computer 100 of each of users A and B, an HTML browser and a CP browser capable of interpreting VRML content are operating. The HTML browser is Netscape Navigator of Netscape Communications or Internet Explorer of Microsoft Corp. for example.

The user computer 100 is connected to the Internet 10 by going through a predetermined procedure such as executing dial-up IP connection to a nearby access point (AP). In addition, the user computer 100 access the WWW server 25 through the HTML browser according to HTTP protocol. Then, retrieving a VRML file for describing the shared virtual world from the WWW server 25, the user computer 100 passes the VRML file to the CP browser.

The CP browser analyzes the VRML file and displays it on a browser screen. If the address of the CP server

22 is specified in the VRML file, the CP browser attempts connection to the CP server 22. CP browsers that have retrieved the same VRML file connect (namely, log in) to the same CP server 22, so that these CP browsers can share the VRML scene described by the retrieved file, namely the same three-dimensional virtual world.

When the connection to the CP server 22, namely the log-in to the shared virtual world has been successful, the communication thereafter is carried out is by use of a predetermined server-client protocol (referred to herein as VSCP (Virtual Society Server Client Protocol) for the communication between the CP server 22 and the CP browser. This VSCP includes a capability of notifying the CP server 22 of changes made by the user by use of the CP browser and a capability of notifying another CP browser of the notified information by the CP server 22.

The CP server 22 can restrict the distribution of information required by each user (namely, the information to be sent to each CP browser) by use of an aura algorithm. An aura denotes an area around an avatar, namely an area in which the user is interested as described before. The information about things outside an aura is regarded as out of interest and therefore not sent to the CP browser. Application of the aura algorithm

can limit the quantity of the information to be distributed, thereby preventing the network traffic to each log-in user from exceeding a specified channel capacity.

The shared virtual world provided by the CP server 22 contains various objects such as the avatars of users and pets (virtual creatures bred by avatars). These objects, the behaviors of objects, and other virtual world applications are shared by users and therefore, these are herein referred to as shared applications.

The AO (Application Object) on the AO server 23 manages the shared applications. The development environments of the AO are mainly Java and C++ programming languages. The AO provides API (Application Programming Interface) for controlling the access to the internal information of the CP server 22, an event handler such as a timer, and the shared objects managed by the AO. The shared objects herein include avatars appearing on the browser of each user computer (namely, shared by users) and the virtual creatures (pets) bred by avatars.

The AO server 23 can communicate with the CP server 22 by use of a predetermined application protocol. Therefore, the CP server 22 and the AO server 23 need not

operate on a single server machine; as shown in FIG. 1, they can be scalable architectures existing as independent computer systems.

FIG. 3 shows the behavior mechanism of the AO associated with the present embodiment by way of example. In the example shown, a behavior in which a pet (a shared application) of an avatar produces a sound when the log-in user of the avatar clicks the pet is shared by log-in users.

When the AO server 23 connects to the CP server 22, the AO server 23 issues a request to the CP server 22 for adding the shared objects managed by the AO server 23 to the shared virtual space (S1).

The CP server 22 transfers this request to all CP browsers connected to the CP server 22. Consequently, the shared objects appear on each CP browser, namely the monitor of each currently log-in user (S2).

If a user selects (or clicks) a shared object on the CP browser (S3), the corresponding script is activated on the CP browser (S4). This script sends a message to the CP server 22 (S5).

The CP server sends this message to the AO server 23 managing the selected shared object (S6). The AO server 23 executes message processing and returns the

processed message to all other CP browsers via the CP server 22 (S7). As a result, the message is passed to the corresponding shared object of each of the other CP browsers, executing the same processing on the corresponding shared object (S8).

3. Telephone Capabilities in Community System

As described, in the community system associated with the present invention, the quantity of information to be distributed is limited by use of the aura algorithm, thereby preventing the network traffic to each log-in user from exceeding a specified channel capacity.

However, as described before, the aura algorithm has a drawback that an object outside an aura becomes incommunicado (refer to FIG. 4). This does not pose a serious problem by setting the aura to a size large enough for each user to view at a glance on the monitor screen in the case of a normal interaction with avatars.

If a virtual world itself has a vast expanse, however, and an event in which plural users participate at a time is to be held, there occurs a demand for making activities by communicating with remote avatars.

In the community system associated with the present embodiment, such infrastructures for implementing the communications with remote avatars as mobile telephone,

PHS, and public telephone are introduced in each shared virtual space (these telephone systems are hereafter referred to also as virtual telephones). Consequently, avatars can make communication with each other by use of mobile telephones (refer to FIGS. 5 and 6). The telephone is a device for supporting realtime communication between remote users also in the real world. In conversation through virtual telephones, a calling avatar need not bring a called avatar into the aura of the calling avatar or vice versa. The virtual telephone also allows avatars not always certain in whereabouts in a shared virtual space to communicate each other.

In addition to the basic capability of one-to-one real-time communication between avatars in the same shared virtual space, the telephone introduced in a shared virtual space may have various features of the mobile telephone used in the real world. For example, these features include a telephone directory capability by which the names and telephone numbers are registered beforehand and only a registered name need to be selected for dialing, an incoming call rejection directory capability by which specific users are registered beforehand to reject the receipt of their calls, and a nuisance call rejection capability by which the calls

from the specified users registered in the incoming call rejection directory are rejected.

The present embodiment also adds to the virtual telephone of each avatar a capability of making communication with another virtual world or with the real world.

Another virtual world herein denotes a different virtual space built and provided on the WWW of the Internet 10 by a server other than the CP server 22 or a virtual space built and provided on the WWW by a service provider of a different parent organization. This another virtual world may be provided by a server on a small-scale network other than the LAN 20. Communication with another virtual world denotes calling by telephone an avatar living in this another virtual world from the shared virtual world associated with the present embodiment (refer to FIG. 7).

The real world herein denotes the real world or space other than any digital space built in computing environment. The communication in the real world is carried out via the public telephone network 30 including PSTN, ISDN, cellular, and PHS systems. Namely, the communication with the real world from a virtual mobile telephone denotes calling user in the real world from the

shared virtual world associated with the present embodiment (refer to FIG. 8). Alternatively, this communication may be carried out by use of electronic mail.

FIG. 9 shows a GUI (Graphical User Interface) screen provided on the computer 100 of a user who is logging in the community system associated with the present embodiment.

This GUI screen is displayed by the CP browser which interprets VRML. As shown, the CP browser frame displays a scene around an avatar (or a scene in the visual range of that avatar) in a shared virtual world. As shown, a pet (a virtual creature) bred by the avatar may be displayed. Remarks made by the avatar or its pet are shown in a speech balloon. The user can make the avatar have a stroll in the shared virtual space by operating the mouse cursor within the browser frame. The GUI screen may also have features such as zoom-in/zoom-out, rotation, and jump of the displayed scene.

In addition, the GUI screen associated with the present embodiment has "Communications Tool" window. "Communications Tool" window has functional buttons for calling such various capabilities necessary for establishing the communication with other avatars (or

their users) and other activities in the virtual world as chat, letter, PHS, and map of shared virtual world.

When "PHS" button is pressed, "Telephone Directory" window appears as shown in FIG. 10. "Telephone Directory" window shows a list box listing entries of the names registers avatars or registered users (or the handles of registered users) and their contact addresses. Contact addresses herein denote the numbers of mobile telephones or PHS telephones of the avatars in the shared virtual world associated with the present embodiment and other virtual worlds and the numbers of mobile telephones or PHS telephones or electronic mail addresses of the users in the real world.

Clicking "New" button in "Telephone Directory" window can enter a new contact address into the telephone directory. Clicking "Delete" button can delete a selected entry (highlighted) from the telephone directory. Clicking "View" button can display the property of an avatar (or user) corresponding to the selected entry.

Clicking "Call" button causes "PHS Talk" window to pop up. In "PHS Talk" window, the user calls a destination of communication, an avatar selected by the telephone directory for example and enters a reply message.

FIG. 11 illustrates "PHS Talk" window. As shown, "PHS Talk" window includes "Name" field and "Telephone Number" field in which the name of telephone number of a called party are entered, "Send" field in which a message text to be sent is entered, and "Receive" field in which a received message is displayed. When "PHS Talk" window is called from the telephone directory, the user name (or avatar name) and telephone number of the entry selected by the list box of the telephone directory are automatically entered in the corresponding fields.

In addition, "PHS Talk" window has "Call" button for starting a calling operation, "Store" button for storing the entry made in the window, and "Permanent Reject" button for semipermanently rejecting the termination of calls from the users or avatars corresponding to the entered names and telephone numbers. When "Call" button is clicked, operations for calling the destination and transferring messages start.

Instead of PHS and mobile telephones, a public telephone box (described before) may be installed in the shared virtual world. For example, when an avatar searches the shared virtual world and accommodates a retrieved public telephone box in its aura, the communication tool having "Public Telephone" button

appears (refer to FIG. 12). An operational procedure to be followed after clicking "Public Telephone" button is as described with reference to FIG. 10.

The following describes the processing for making a telephone call (or sending a message) from the shared virtual world to the same virtual world, another virtual world, and the real world.

FIG. 13 is a flowchart indicative of the processing for making a telephone call by user A in the shared virtual world through the avatar of this user. The following describes each step of this processing.

First, user A clicks "PHS" button arranged in "Communications Tool" (step S101) to call the PHS or telephone capability of the virtual world. "Telephone Directory" window appears on the CP browser screen. Instead of using the PHS at a given place in the shared virtual world, user A may accommodate a public telephone box into the aura of user A and click "Public Telephone" box.

Next, user A selects a desired telephone number entry from the list box in "Telephone Directory" window and clicks "Call" button (step S102).

The telephone number selected here is the number of the PHS or mobile telephone of a called avatar in the

present shared virtual world, the number of the PHS or mobile telephone of a called avatar in another virtual world, or the number of the PHS or mobile telephone of the electronic mail address of a called user in the real world. It should be noted that, before entering the telephone numbers of destination avatars into the telephone directory, the telephone numbers must be exchanged between avatars, the description of which will be skipped because this process is not directly related to the gist of the present invention.

Upon clicking "Call" button in "Telephone Directory" window, "PHS Talk" window appears. In "PHS Talk" window, the user can enter the name and telephone number of a called party, check the entries, and input a message text to be sent, for example. Next, the user clicks "Call" button in "PHS Talk" window (step S103), upon which a calling operation starts (step S104).

The calling by user A is communicated to the AO server 23 via the CP server 22 (step S121).

The AO server 23 determines whether the called party is inside the same shared virtual world or not (step S122).

If the called party is found inside the same shared virtual world, the AO server 23 searches for the avatar

FIG. 14 is a flowchart indicative of the processing procedure for calling from a PHS in the real world to the avatar of user B in the shared virtual world. The following describes each step of this processing.

When a user makes a telephone call by use of a PHS in the real world and sends a message (step S233), the message is passed to the AO server 23 through the gateway system 40 (step S232 and step S231).

The AO server has a table for managing the telephone numbers of the users or avatars under the control of the AO server 23. Upon reception of the call from the real world through the gateway system 40, the AO server 23 searches this table for user identification information (step S221).

If the AO server 23 is unsuccessful in retrieving the user identification information, it indicates that the corresponding user does not exist in the shared virtual world. Then, the processing by the AO server 23 goes to decision "No" of step S222, thereby notifying the PHS of the real world through the gateway system 40 of the fact that the desired user or avatar does not exist in the shared virtual world.

If the AO server 23 is successful in retrieving the user identification information, it indicates that the

corresponding user is inside the shared virtual world. Therefore, the processing by the AO server 23 goes to decision "Yes" of step S222 to search for the avatar of the called party (user B) (step S223). Actually, the AO server 23 searches the AO, which is an avatar managing entity.

To connect the call to the avatar of the called party, predetermined connection processing is executed between AOs.

When the connection has been established, "PHS Talk" window (refer to the above description and FIG. 11) appears in the PC browser of user B, the called party. In this "PHS Talk" window, user B can check the name and telephone number of the calling party (in this case, the PHS in the real world) (provided that the number display capability is active). In addition, in "PHS Talk" window, user B can display the received message and input a message to be sent.

While the connection is kept between the avatars of user A and user B, messages can be transferred anytime. For example, when sending a message from a PHS in the real world, the AO server 23 executes message receive processing (step S225). In "PHS Talk" window of user B, the received message is displayed in "Receive" field

(step S212).

When a message is sent from user B, user B inputs a message text to be sent in "Send" field of "PHS Talk" window and sends this message (step S213). This message is then passed to the AO server 23 through the CP server 22, upon which the processing for sending the message to the PHS in the real world is executed.

While the preferred embodiments of the present invention have been described using specific terms, such description is for illustrative purposes only, and it is to be understood that changes and variations may be made without departing from the spirit or scope of the appended claims.

As described and according to the invention, a conversation support system and a conversation support method are provided that allow two or more users to simultaneously participate, for realtime communication, in a virtual world having a predetermined spatial expanse built on a computer network such as the Internet.

In addition, a conversation support system and a conversation support method are provided that allow users to communicate each other without making a face-to-face meeting in a shared virtual world having a spatial expanse built on a computer network.

Further, a conversation support system and a conversation support method are provided that allow users to communicate each other beyond a single shared virtual world.

Moreover, a conversation support system and a conversation support method are provided that allow users to communicate each other even if one of users between whom communication is to be established is not in a shared virtual world having a spatial expanse built on a computer network.

09714637 111600

What is claimed is:

1. A conversation support system for supporting a plurality of users in having a virtual conversation in a shared virtual space built and provided on a computer network, comprising:

enrolling means for enrolling an avatar of a log-in user into said shared virtual space;

imparting means for imparting a virtual mobile telephone to each avatar in said shared virtual space, said virtual mobile telephone being usable therein;

determination means for determining, in response to a call from said virtual mobile telephone, whether a calling party who originated said call exists in said shared virtual space; and

connecting means for executing connection processing in accordance with a decision made by said determination means.

2. The conversation support system according to claim 1, wherein, if said calling party originated said call from a telephone in real world, said connecting means establishes connection with said calling party through a public telephone network in the real world and/or executes message transfer.

3. The conversation support system according to

claim 1, wherein, if said calling party originated said call from a telephone in another virtual space, said connecting means establishes connection with said telephone in another virtual space and/or executes message transfer.

4. The conversation support system according to claim 1, wherein said connecting means receives said call from said telephone in real world and/or said telephone in another virtual space and connects the received call to a virtual mobile telephone of a called avatar in said shared virtual space.

5. A conversation support system for supporting a plurality of users in having a virtual conversation in a shared virtual space built and provided on a computer network, comprising:

enrolling means for enrolling an avatar of a log-in user into said shared virtual space;

imparting means for imparting a virtual public telephone usable by any enrolled avatar to said shared virtual space at a predetermined place;

determination means for determining, in response to a call from said virtual public telephone, whether a calling party who originated said call exists in said shared virtual space; and

connecting means for executing connection processing in accordance with a decision made by said determination means.

6. The conversation support system according to claim 5, wherein, if said calling party originated said call from a telephone in real world, said connecting means establishes connection with said calling party through a public telephone network in real world and/or executes message transfer.

7. The conversation support system according to claim 5, wherein, if said caller originated said call from a telephone in another virtual space, said connecting means establishes connection with said telephone in another virtual space and/or executes message transfer.

8. A conversation support method for supporting a plurality of users in having a virtual conversation in a shared virtual space built and provided on a computer network, comprising the steps of:

enrolling an avatar of a log-in user into said shared virtual space;

imparting a virtual mobile telephone to each avatar in said shared virtual space, said virtual mobile telephone being usable therein;

determining, in response to a call from said virtual mobile telephone, whether a calling party who originated said call exists in said shared virtual space; and

executing connection processing in accordance with a decision made in said determination step.

9. The conversation support method according to claim 8, wherein, if said calling party originated said call from a telephone in real world, said connecting step establishes connection with said calling party through a public telephone network in the real world and/or executes message transfer.

10. The conversation support method according to claim 8, wherein, if said calling party originated said call from a telephone in another virtual space, said connecting step establishes connection with said telephone in another virtual space and/or executes message transfer.

11. The conversation support method according to claim 8, further comprising the steps of:

receiving a call from a telephone in real world and/or a telephone in another virtual space;

determining whether said call is directed to an avatar existing in said shared virtual space; and

if a decision made in the determination step is affirmative, connecting said call to a virtual telephone of said avatar.

12. A conversation support method for supporting a plurality of users in having a virtual conversation in a shared virtual space built and provided on a computer network, comprising the steps of:

enrolling an avatar of a log-in user into said shared virtual space;

imparting a virtual public telephone usable by any enrolled avatar to said shared virtual space at a predetermined place;

determining, in response to a call from said virtual public telephone, whether a calling party who originated said call exists in said shared virtual space; and

executing connection processing in accordance with a decision made in said determination step.

13. The conversation support method according to claim 12, wherein, if said calling party originated said call from a telephone in real world, said connecting step establishes connection with said calling party through a public telephone network in the real world and/or executes message transfer.

14. The conversation support method according to claim 8, wherein, if said calling party originated said call from a telephone in another virtual space, said connecting step establishes connection with said telephone in another virtual space and/or executes message transfer.

15. A conversation support method for supporting an activity of an avatar in a shared virtual space built and provided on a computer network, comprising the steps of:

receiving a request for sending a message from said avatar;

determining whether a destination of said message exists in said shared virtual space; and

executing connection processing in accordance with a decision made by the determining step.

16. The conversation support method according to claim 15, wherein, if said destination of said message is found in real world, said connecting step establishes connection with said destination through a public telephone network in real world and/or executes message transfer.

17. A conversation support method for supporting an activity of an avatar in a shared virtual space built

and provided on a computer network, comprising the steps
of:

receiving a request for sending a message from a source in real space through a public telephone network in real world;

determining whether a destination of said message exists in said shared virtual space; and

if a decision made by the determining step is affirmative, sending said message to said avatar.

18. A program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, said computer program comprising the steps of:

enrolling an avatar of a log-in user into said
shared virtual space;

imparting a virtual public telephone usable by any enrolled avatar to said shared virtual space at a predetermined place;

for determining, in response to a call from said virtual public telephone, whether a calling party who originated said call exists in said shared virtual space;

and

executing connection processing in accordance with a decision made in said determination step.

19. A program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, said computer program comprising the steps of:

enrolling an avatar of a log-in user into said shared virtual space;

imparting a virtual public telephone usable by any enrolled avatar to said shared virtual space at a predetermined place;

determining, in response to a call from said virtual public telephone, whether a calling party who originated said call exists in said shared virtual space; and

executing connection processing in accordance with a decision made in said determination step.

20. A program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual

conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, said computer program comprising the steps of:

receiving a request for sending a message from said avatar;

determining whether a destination of said message exists in said shared virtual space; and

executing connection processing in accordance with a decision made in the determining step.

21. A program storage medium storing a computer program in a computer readable form for executing processing on a computer system for supporting a virtual conversation in which a plurality of users can participate in a shared virtual space built and provided on a computer network, said computer program comprising the steps of:

receiving a request for sending a message from a source in real space through a public telephone network in real world;

determining whether a destination of said message exists in said shared virtual space; and

if a decision made in the determining step is affirmative, sending said message to said avatar.

ABSTRACT OF THE DISCLOSURE

A conversation support system and a conversation support method for providing a realtime communications environment in which a plurality of users simultaneously participate in a virtual world built and provided on a computer network for realtime talking. A shared virtual space accommodates remote communications infrastructures such as mobile telephone, PHS, and public telephone. Avatars can have a talk with each other by use of these infrastructures regardless of the locations of the communicating avatars, namely regardless of whether each avatar is inside or outside its aura. Namely, the avatars can communicate each other beyond a single shared virtual world. The PHS owned by each avatar can communicate with any PHS in another virtual world or even in the real world.

FIG. 1




FIG.2




FIG. 3




FIG. 4




FIG. 5




FIG. 6




FIG. 7




FIG. 8




FIG. 9




FIG.10





FIG.11



CP BROWSER
SCREEN

PHS TALK
WINDOW

FIG.12




FIG. 13





FIG. 14



Declaration and Power of Attorney For Patent Application

特許出願宣言書及び委任状

Japanese Language Declaration

日本語宣言書

下記の氏名の発明者として、私は以下の通り宣言します。

As a below named inventor, I hereby declare that:

私の住所、私書箱、国籍は下記の私の氏名の後に記載された通りです。

My residence, post office address and citizenship are as stated next to my name.

下記の名称の発明に関して請求範囲に記載され、特許出願している発明内容について、私が最初かつ唯一の発明者（下記の氏名が一つの場合）もしくは最初かつ共同発明者であると（下記の名称が複数の場合）信じています。

I believe I am the original, first and sole inventor (if only one named is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled.

SHARED VIRTUAL SPACE CONVERSATION SUPPORT
SYSTEM AND METHOD AND PROGRAM RECORDING
MEDIUM

上記発明の明細書（下記の欄でx印がついていない場合は、本書に添付）は、

the specification of which is attached hereto unless the following box is checked:

☐ __月__日に提出され、米国出願番号または特許協定条約国際出願番号を____とし、
（該当する場合）____に訂正されました。☐ was filed on ____ as United States Application Number or PCT International Application Number ____ and was amended on ____ (if applicable).

私は、特許請求範囲を含む上記訂正後の明細書を検討し、内容を理解していることをここに表明します。

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to above.

私は、連邦規則法典第37編第1条56項に定義されたとおり、特許資格の有無について重要な情報を開示する義務があることを認めます。

I acknowledge the duty to disclose information which is material to patentability as defined in Title 37, Code of Federal Regulations, Section 1.56.

私は、米国法典第35編119条(a)-(d)項又は365条(b)項に基づき下記の、米国以外の国の少なくとも一カ国を指定している特許協力条約365(a)項に基づき国際出願、又は外国での特許出願もしくは発明者証の出願についての外国優先権をここに主張するとともに、優先権を主張している、本出願の前に出願された特許または発明者証の外国出願を以下に、枠内をマークすることで、示しています。

I hereby claim foreign priority under Title 35, United States Code, Section 119(a)-(d) or 365(b) of any foreign application(s) for patent or inventor's certificate, or 365(a) of any PCT International application which designated at least one country other than the United States, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's certificate, or PCT International application having a filing date before that of the application on which priority is claimed.

Prior Foreign Application(s)
外国での先行出願Priority Not Claimed
優先権主張なしP11-337105
(Number)
(番号)JAPAN
(Country)
(国名)29 NOVEMBER 1999
(Day/Month/Year Filed)
(出願年月日)☐(Number)
(番号)(Country)
(国名)(Day/Month/Year Filed)
(出願年月日)☐(Number)
(番号)(Country)
(国名)(Day/Month/Year Filed)
(出願年月日)☐

0097 2647 260

Declaration and Power of Attorney For Patent Application

特許出願宣言書及び委任状

Japanese Language Declaration

日本語宣言書

私は、第35編米国法典119条(e)項に基いて下記の米国特許出願規定に記載された権利をここに主張いたします。

(Application No.)

(出願番号)

(Filing Date)

(出願日)

I hereby claim the benefit under Title 35, United States Code, Section 119(e) of any United States provisional application(s) listed below.

(Application No.)

(出願番号)

(Filing Date)

(出願日)

私は、下記の米国法典第35編120条に基いて下記の米国特許出願に記載された権利、又は米国を指定している特許協力条約365条(c)に基づく権利をここに主張します。また、本出願の各請求範囲の内容が米国法典第35編112条第1項又は特許協力条約で規定された方法で先行する米国特許出願に開示されていない限り、その先行米国出願書提出日以降で本出願書の日本国内または特許協力条約国際提出日までの期間中に入手された、連邦規則法典第37編1条56項で定義された特許資格の有無に関する重要な情報について開示義務があることを認識しています。

(Application No.)

(出願番号)

(Filing Date)

(出願日)

I hereby claim the benefit under Title 35, United States Code, Section 120 of any United States application(s), or 365(c) of any PCT International application designating the United States, listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States or PCT International application in the manner provided by the first paragraph of Title 35, United States Code, Section 112, I acknowledge the duty to disclose information which is material to patentability as defined in Title 37, Code of Federal Regulations, Section 1.56 which became available between the filing date of the prior application and the national or PCT International filing date of application.

(Status: Patented, Pending, Abandoned)

(現況: 特許許可済、係属中、放棄済)

(Application No.)

(出願番号)

(Filing Date)

(出願日)

(Status: Patented, Pending, Abandoned)

(現況: 特許許可済、係属中、放棄済)

私は、私自身の知識に基づいて本宣言書中で私が行なう表明が真実であり、かつ私の入手した情報と私の信じることに基づく表明が全て真実であると信じていること、さらに故意になされた虚偽の表明及びそれと同等の行為は米国法典第18編第1001条に基づき、罰金または拘禁、もしくはその両方により処罰されること、そしてそのような故意による虚偽の声明を行なえば、出願した、又は既に許可された特許の有効性が失われることを認識し、よってここに上記のごとく宣誓を致します。

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may be jeopardize the validity of the application or any patent issued thereon.

委任状: 私は下記の発明者として、本出願に関する一切の手続きを米特許商標局に対して遂行する弁理士または代理人として、下記の者を指名いたします。(弁理士、または代理人の氏名及び登録番号を明記のこと)

POWER OF ATTORNEY: As a named inventor, I hereby appoint the following attorney(s) and/or agent(s) to prosecute this application and transact all business in the Patent and Trademark office connected therewith (*list name and registration number*)

Karl A. Limbach 18,689
George C. Limbach 19,305
John K. Uilkema 20,282
Neil A. Smith 25,441
Veronica C. Devitt 29,375
Ronald L. Yin 27,607
Gerald T. Sekimura 30,103
Michael A. Stallman 29,444
Philip A. Girard 28,848
Michael J. Pollock 29,098

Steven M. Everett 30,050
Alfred A. Equitz 30,922
Charles P. Sammut 28,901
Mark C. Pickering 36,239
Patricia Coleman James 37,155
Kathleen A. Frost 37,326
Alan A. Limbach 39,749
Douglas C. Limbach 35,249
Seong-Kun Oh* 41,815
Kyla L. Harriel
* Recognition under 37 CFR 10 9(b)

Mayumi Maeda 40,075
Charles L. Hamilton 42,624
Andrew V. Smith 43,132
Eric N. Hoover 37,355
Frank J. Mycroft 46,946
Robert M. McConnell 46,912
J. Thomas McCarthy 22,420
Joel G. Ackerman 24,307
Roger S. Sampson 44,314
Susan M. Schmitt 34,427
Edward B. Weller 37,468

Declaration and Power of Attorney For Patent Application

特許出願宣言書及び委任状

Japanese Language Declaration

日本語宣言書

書類送付先	Send Correspondence to: Charles P. Sammut, Esq. Limbach & Limbach L.L.P. 2001 Ferry Building San Francisco, CA 94111-4262
直接電話連絡先： (名前及び電話番号)	Direct Telephone Calls to: (name and telephone number) Charles P. Sammut (415) 433-4150
唯一または第一発明者名	Full name of sole or first inventor: KOUICHI MATSUDA
発明者の署名	Inventor's signature
日付	Date
住所	Residence TOKYO, JAPAN
国籍	Citizenship JAPAN
私書箱	Post Office Address c/o SONY CORPORATION 7-35, Kitashinagawa 6-chome Shinagawa-ku, Tokyo, 141-0001 JAPAN

00744537 41600